

**BRUHATH BENGALURU MAHANAGARA PALIKE**

Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

NO:BBMP/EE/YNK.D/EPMT-02/2020-21 Dt:06-5-2020

**APPROVED TENDER SCHEDULE -'B'**

Item 27

Name of Work :- Improvements and Asphaltting to roads at Prakruthi layout in chowdeshwari ward no - 02 of yelahanka sub division

| Sl | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Unit | Approved Qty | Rate quoted by the contractor approved rates<br>Sri M N RAMAIAH |                                             |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------|-----------------------------------------------------------------|---------------------------------------------|
|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |              | Rate                                                            | Rate in Words                               |
| 1  | KSRRB 300: Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 m and an average lift upto 0.5 m. excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)                                                                                                                                                                             | Cum  | 270.64       | 188.00                                                          | One Hundred EightyEight Only                |
| 2  | KSRB M2100-10:Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @ 0.89 cum and fine aggregates @ 0.46 cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works,                                                                                                                                                                               | Cum  | 37.34        | 4734.00                                                         | Four Thousand Seven Hundred ThirtyFour Only |
| 3  | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2000. Including cost of materials, labour, HOM complete as per specifications. (Page No.271. Item No,37.59.2 of PW, P&IWD S.R 2018-19) | Cum  | 73.84        | 6173.00                                                         | Six Thousand One Hundred SeventyThree Only  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |        |          |                                           |
|---|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|----------|-------------------------------------------|
|   | KSRRB M2300-14: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour HOM of machinery complete as per specifications. Specification NO. MORTH Specification No.1600 & 2200 TMT Bars Fe 500. (Page No. 239. Item No. 29.29.2 of PW. P&I WTD S.R 2018-19) | Tonne | 4.83   | 64603.00 | SixtyFour Thousand Six Hundred Three Only |
| 5 | Providing and Fixing RCC pre cast cover Slab 100mm thick for drain made out of CC 1:1.5:3 and jelly 20mm Down size with steel reinforcement including form work, lift charges, curing and concrete finished on both sides etc., Complete As per drawing and direction of Engineer IN charge. (Data Rate)                                                                                                                                                                                                                                                             | Sqm   | 167.85 | 2040.00  | Two Thousand Fourty Only                  |
| 6 | Providing and Fixing RCC pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work, laid and lift charges, curing and concrete finished surfaces on both sides etc., complete. As per Engineer IN charge. (Data Rate).                                                                                                                                                                                                                                                                           | Sqm   | 33.00  | 4730.00  | Four Thousand Seven Hundred Thirty Only   |
| 7 | KSRRB M300-14: Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification No.30. Loading and unloading with 8km lead. (P. No-143, I.No-19.14)                                                                                                                                                                 | Cum   | 234.50 | 56.00    | FiftySix Only                             |
| 8 | Construction of granular sub-base Grading V as Sub-Base and drainage layer by providing coarse graded crushed stone aggregates of granite/trap/basalt material, mixing in mechanical mix plant at OMC. Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision. Page No. 153. Item                                                                                  | Cum   | 100.50 | 1742.00  | One Thousand Seven Hundred FourtyTwo Only |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |     |        |         |                                             |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|---------|---------------------------------------------|
|    | KSRRB M400-17: Providing, Laying, Spreading and Compacting crushed stone aggregates of granite/ trap/ Basalt to wet mix macadam specifications including premixing the material with water at OMC in Mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406. Page No. 155. Item No. 20.18.                                                                                                                          | Cum | 167.50 | 1747.00 | One Thousand Seven Hundred FourtySeven Only |
| 10 | KSRRB M500-6: Providing and Supplying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg /sqm using mechanical means complete as per specifications Clause 502 of MORTH Clause 502 of MORTH V revision (P.No-158, Item No. 21.6).                                                                                                                                                                                                                                                                                              | Sqm | 670.00 | 25.00   | TwentyFive Only                             |
| 11 | KSRRB M500-17: Providing and laying Dense Graded Bituminous Macadam using crushed aggregates of crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete in all respects complete as per specifications. MORTH Specification No,507. Using 100/120 TPH capacity HMP with sensor paver Gr-II (50mm to 75mm) with 4.5% VG-30 Bitumen (Page No. 160. I.No-21.17.6) | Cum | 33.50  | 5760.00 | Five Thousand Seven Hundred Sixty Only      |
| 12 | KSRRB 500-7: Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 0.25kg per sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 (Page No. 158. Item No. 21.7)                                                                                                                                                                                                                                                                          | Sqm | 670.00 | 11.00   | Eleven Only                                 |

|                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |     |       |         |                                         |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|---------|-----------------------------------------|
| <p>Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015. Do- using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4% of modified bituminous binder consisting of 4.97% of VG-30 Bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) (Page No. 171. Item NO.21.78.12)</p> | Cum | 20.10 | 6770.00 | Six Thousand Seven Hundred Seventy Only |
| <p>14 KSRRB M800-13: Road marking with Hot Applied 'Thermoplastic' Compound with Reflectorizing Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads at 250gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35.The Finished surface to be level , Uniform and free from streaks and holes complete as per Specifications. MORTH Specification NO.803 (P.No-182, I.No-24.15)</p>                                                                                                                                                                                                                                      | Sqm | 26.80 | 397.00  | Three Hundred NinetySeven Only          |

*m.m. Ramesh*  
Signature of the Contractor

*[Signature]*  
Executive Engineer,  
Yelahanka Division,  
BBMP, Bengaluru-64.